

Operational Instructions

OI - 3.4 | Cut & Fill [Road Box]

Revision:

A

Section:

3.0 - Infrastructure Stage 1

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
• In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) • Work areas are to be segregated in accordance with MIDA Operational Standard - 2.5 - Segregation - Groundworker Only Area	• We must pre-agree stockpile locations with the client • Before commencing the cut or fill operation, please ensure the engineer has given correct datums (either by machine control or travellers) • Check the specification before we start – are we filling to a pre-agreed earthworks specification? • What is the testing regime? Have you booked the necessary tests? • Has the Local Authority been consulted?
QA Checks & Actions	Operational Standard - References
• Pre & Post strip surveys to be completed by the engineering department • Photograph the completed area and include in your photographic daily diary	• MIDA Operational Standard - 2.5 - Segregation - Groundworker Only Area