

Operational Instructions

OI - 4.10 | Breedon Gravel Footpath

Revision:

B

Section:

4.0 - Infrastructure Stage 2

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
● In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) ● Working areas are to be segregated in accordance with MIDA Operational Standard - 2.4 - Segregation - General Working Area	● The suitability of the sub-formation ● That the sub-base is correctly compacted ● The finished level and how that interacts with the other open space features – have we highlighted drainage / ponding issues? ● The laying specification of the gravel – how thick should it be placed? What thickness should it roll down to? ● The specification of the roller being used – does it release the correct volume of water per pass? ● The timber edgings are laid in accordance with MIDA Operational Standard - 4.1 - Timber Edging ● The gravel is clean from muck and debris – tip loose gravel on polythene sheet
QA Checks & Actions	Operational Standard - References
● Photograph the completed area and include in your photographic daily diary	● MIDA Operational Standard - 2.4 - Segregation - General Working Area ● MIDA Operational Standard - 4.1 - Timber Edging