

Operational Instructions

OI - 4.2 | Tactile Paving

Revision: C

Section: 4.0 - Infrastructure Stage 2

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
● In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) ● Working areas are to be segregated in accordance with MIDA Operational Standard - 2.4 - Segregation - General Working Area or MIDA Operational Standard - 2.6 - Segregation - Public Working Area ○ Wherever we are operating within trafficked carriageways, we must be working under Chapter 8 regulations	● Inform the Local Authority to let them know we are starting works – they may want to inspect ● Depth of tactile paving to be checked before ordering ● Please ensure that tactile paving is installed prior to any footpath wearing course ● Tactiles are to be laid on a wet mixed, sand and cement screed – do not lay dry ● Ensure the tactiles are set out properly and line up with the opposite side of the road ● Please ensure that you review the Local Authority detail – do they have edgings? Are there block paved strips? ● Check the kerb height – Max 6mm at crossing point
QA Checks & Actions	Operational Standard - References
● Photograph the completed area and include in your photographic daily diary	● MIDA Operational Standard - 2.4 - Segregation - General Working Area ● MIDA Operational Standard - 2.6 - Segregation - Public Working Area