

Operational Instructions

OI - 4.3 | Adoptable Footways

Revision:

A

Section:

4.0 - Infrastructure Stage 2

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
● In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) ● Working areas are to be segregated in accordance with MIDA Operational Standard - 2.4 - Segregation - General Working Area or MIDA Operational Standard - 2.6 - Segregation - Public Working Area ○ Wherever we are operating within trafficked carriageways, we must be working under Chapter 8 regulations	● Inform the Local Authority to let them know we are starting works – they may want to inspect ● Have all mains’ services been installed prior to footway construction? ● Check the sub-formation is suitable before commencing ● Confirm the depths of construction and specification before commencing ● Have we informed the Local Authority that the works are progressing? ● Ensure all of the service ironwork is raised – is it at the correct level? ● Does the asphalt need to be machine laid in line with LA specification? ● Tac coat to be applied before wearing
QA Checks & Actions	Operational Standard - References
● Photograph the completed area and include in your photographic daily diary	● MIDA Operational Standard - 2.4 - Segregation - General Working Area ● MIDA Operational Standard - 2.6 - Segregation - Public Working Area