

Operational Instructions

OI - 5.17 | Screen Walls

Revision:

B

Section:

5.0 - Plot Groundworks Stage 1

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
● In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) ● Ensure safe access is maintained for sub-contract bricklayers ● Foundations are to be segregated in accordance with MIDA Operational Standard - 2.7 - Segregation - Foundations	● Screen wall foundations must be installed at Stage 1 – do not leave until external stage ● Have you checked the foundation design? ● Ensure your foundation is dug to the designed BOF level ● Have you checked the boundary line of the “fare-face” of the wall? Does it line up with the connecting wall, garage etc.? ● If the wall is connecting to another structure – do we have a connection detail? ● Movement joints and pier positions to be installed to centres as per design ● Masonry is to be cleaned and left free from staining before handing over to the client ● Consider if engineering brick DPC is required
QA Checks & Actions	Operational Standard - References
● Form QMF 23 – CML Handover ● Photograph the completed area and include in your photographic daily diary	● MIDA Operational Standard - 2.7 - Segregation - Foundations