

Operational Instructions

OI - 6.2 | Drain Test & Connection Check

Revision:

A

Section:

6.0 - Plot Groundworks Stage 2

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
• In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) • Working areas are to be segregated in accordance with MIDA Operational Standard - 2.4 - Segregation - General Working or MIDA Operational Standard - 2.6 - Segregation - Public Working Area	• The drain test works are to be completed and checked in advance of the building control visit • Please ensure that the correct size testing bags are utilised in each instance • Please flush the storm and foul drainage from the house and check that all the runs are connected to the outfall manhole • Ensure that the main line sewer (in the road) is lifted and checked
QA Checks & Actions	Operational Standard - References
• Form QMF 23 – CML Handover	• MIDA Operational Standard - 2.4 - Segregation - General Working Area • MIDA Operational Standard - 2.6 - Segregation - Public Working Area