

Operational Instructions

OI - 6.3 | Slabbing

Revision:

B

Section:

6.0 - Plot Groundworks Stage 2

Visual Aids



Information

Task Specific Safety Checks & Notes	Operational Checks
● In the first instance, please ensure you have referred to your site-specific Risk Assessments & Method Statements (RAMS) ● Working areas are to be segregated in accordance with MIDA Operational Standard - 2.4 - Segregation - General Working Area ○ Liaise with the client's site team to ensure that other trades respect our work areas and front and/or rear doorways are closed off	● Have you checked the slabbing specification, size and laying pattern? ● Ensure the sub-formation is adequate ● Has the sub-base been installed to the correct levels and is correctly compacted with a whacker plate? ● A sharp sand and cement screed is to be mixed on site to the correct specification and laid as bedding material ● Ensure that slabs are laid to the correct designed levels and falls ● Sweep and clean all areas once works have been completed ● Adequately segregate the work area upon completion to prevent trades from walking on the slabs ● No crushed concrete to be used directly under slabs (NHBC requirement)
QA Checks & Actions	Operational Standard - References
● Form QMF 23 – CML Handover ● Photograph the completed area and include in your photographic daily diary	● MIDA Operational Standard - 2.4 - Segregation - General Working Area