

# Operational Standards

|                        |   |          |                                 |
|------------------------|---|----------|---------------------------------|
| OS - 1.15   Drag Skips |   |          |                                 |
| Revision:              | A | Section: | 1.0 - Site Setup & Housekeeping |

## Visual Aids



# Information

| Objective                                                                                                                                             | Application                                                                                          |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"><li>To ensure that material is stored in a manner to prevent waste and maximise production</li></ul>                | <ul style="list-style-type: none"><li>Localised areas where aggregate material is required</li></ul> |
| Site Setup Instructions                                                                                                                               | Operational Responsibilities                                                                         |
| <ul style="list-style-type: none"><li>Skips are to be sited on firm level ground</li><li>Skips are to be located away from excavation edges</li></ul> | <ul style="list-style-type: none"><li>Ensure that skips are LOLER tested</li></ul>                   |