

Operational Standards

OS - 5.4 | Incoming Service Floor Detail

Revision:

B

Section:

5.0 - Plot Groundworks Stage 1

Visual Aids



Information

Objective	Application
To provide a consistent finish to block and beam floors at the point of entry for internal drainage and services	All incoming drainage and service entry points to block and beam floors
Instructions	
- Do not cut the concrete blocks or infill blocks with a saw - Instead, use a core drill to cut a neat consistent hole - The hole is to be a maximum of 110mm dia - Polythene to be taped neatly around the hole - Cap and seal all pipework	