


QUALITY ALERT

Created By: HSEQ Manager

Authorised By: Michael Clorley (Director)

Business:	MIDA Civil Engineering Ltd		ALERT
Title:	Insulating Incoming Water Services	Reference No:	QA13
Issued By:	Sam James	Issue Date:	4/8/23
Type of Alert:	Quality & Compliance		
Subject:	Water Insulation below Suspended floors		
Operatives Affected:	Groundworkers		
Details:	Water service pipes need to be fully insulated where passing through the ground and the ventilated space	Where the floor is of suspended construction, the underfloor water service should be insulated as it passes through the ground and the ventilated space. 	
Action Required:	Early insulation of water feed pipes is recommended. The best time to do this is when the ground floor is being laid		
Further Information:	Mida OI - 5.12 Stage 1 Services NHBC Chapter 8.1.3		
Method for Communication:	Briefing by Site Manager to operatives via TBT Alert to be put up in site office and Canteen		